

ABSTRACT OF THE DISCLOSURE

A deep water subsea tree completion having a distributed temperature
5 sensing system. In a described embodiment, a method of installing an optical
fiber in a well includes the steps of: conveying an optical fiber section into the
well; and monitoring a light transmission quality of the optical fiber section while
the section is being conveyed into the well.